COMPONENT TESTING PROCEDURE

TO TEST	Connect Self-Powered Test Light or Ohmmeter to Terminals	Move Switch to These Positions	A Good Switch Will Indicate
Power and Ground Checks Before Any Other Tests	7 and 6	All Four Window Switches (All Positions)	Open Circuit
	6 and 4, 5, 2, 1, 7, 6, 5, 4	All Four Window Switches (At Rest)	Closed Circuit
Left Front Window Circuit	7 and 4	Down	Closed Circuit
	7 and 5	Up	Closed Circuit
Right Front Window Circuit	7 and 1	Up	Closed Circuit
	7 and 2	Down	Closed Circuit
Left Rear Window Circuit	7 and 2	Down	Closed Circuit
	7 and 6	Up	Closed Circuit
Right Rear Window Circuit	7 and 5	Down	Closed Circuit
	7 and 4	Up	Closed Circuit
Window Lock Switch	7 and 3	Window Lock Switch Toward Door	Closed Circuit
		Window Lock Switch Away From Door	Open Circuit
Automatic Switch	7 and 3	Automatic Switch (Engaged)	Closed Circuit
		Automatic Switch (At Rest)	Open Circuit